

Applies to: All Medical School Departments

GUIDELINES:

Washington

Issued: March 28, 2012 Revised: July 14, 2014

PURPOSE:

To provide guidance to departments for construction projects with an estimated budget of less than \$15,000.)

DEFINITIONS:

N/A

PROCESS:

- 1. Please note the following types of projects <u>must</u> be managed by Capital Projects: Small scale projects with:
 - Hazardous material removal including asbestos.
 - Wall modifications
 - Adding or relocating any door
 - Flooring removal
 - Ceiling replacement
 - Equipment additions/changes, e.g. fume hoods, incubators, -80 degree freezers, cold boxes, etc.
 - HVAC changes
 - Plumbing changes
 - Electrical changes
- 2. After initial review/consultation with Capital Projects, it may be determined that the department can work directly with contractors for the following types of projects with total budgets under \$15,000:
 - Painting
 - Carpeting, VCT and sheet vinyl flooring installation that does not involve asbestos removal
 - Casework modifications
 - Artwork
 - Freestanding furniture (not modular)
 - Addition of telephone or data lines

Capital Projects contact: Steve Sobo, Director, Capital Projects 362-5251

3. Departments are encouraged to take advantage of services available through the School of Medicine for minor renovations including but not limited to: painting, installation of artwork, lock changes, minor casework modifications, furniture moving, flooring and painting.





First Option is utilization of WUSM In-House Construction for all minor renovations

Kerry Johnson

Capital Projects - In House Construction

Supervisor

Phone: 314-202-2775

e-mail: johnsonk@wusm.wustl.edu

A certificate of liability insurance is not required if the above option is used.

Second Option is utilization of local contractors

Contracting with local contractors

Departments also have the option of contracting with local contractors prequalified and approved by WUSM. Contact Capital Projects for a listing of approved contractors for: carpentry, plumbing, mechanical and electrical.

4. Prior to proceeding with the work the department should:

- a) Submit Project Initiation Form (PIF) with description of proposed scope of work
- b) Review the proposed scope with Capital Projects
- c) Follow EH&S Laboratory Closeout Procedures if the scope of work includes laboratories
- d) Contact EH&S if removing <u>any</u> carpeting, vinyl floor tile or lab countertops. EH&S will review the existing floor material and mastic installation for asbestos containment and potential required abatement.

Contact: Brad King 314-825-3203

- e) Contact Infection Prevention if the scope of work involves working in or adjacent to patient care areas. Contact: Sharon Beatty: 314-454-5574
- f) Provide the contractor with a requested scope of work document
- g) Obtain an estimate (minimum 3 bids recommended). In lieu of an estimate work can be performed on an hourly basis.
- h) Review estimate for completeness (recommend review with Capital Projects)
- Obtain a copy of the contractors "Certificate of Liability Insurance" for this specific project naming Washington University as additional insured (only required if contracting companies outside of the School of Medicine)
- j) Forward the "Certificate of Liability Insurance" to Karen Rose from the General Liability Insurance Department for approval.

Karen Trankler Rose

karen.t.rose@wustl.edu phone: 314 935-5561 fax: 314 935-9795

- k) After insurance certificate approval, complete a short form contract (copy attached) and forward to the contractor for their signature for all onsite labor projects. Purchase Orders (PO's) can only be used for purchases where onsite labor is not involved.
 - Note: 1. No modifications are allowed to the WU contract
 - 2. Do Not sign any contractors' proposals/contracts



- 5. Verify the material is in compliance with the criteria for paint, carpet, VCT and sheet vinyl flooring, adhesives and millwork as noted on the attached sheets.
- 6. Notify Protective Services if Contractor is working after business hours

Items to verify prior to hiring an outside contractor for the work listed below:

- Contractor is prequalified. Any Contractor not on the list must be approved by the Resource Management Department before accepting their proposal for the work. The contact person for Resource Management is Greg Parrott (935-4395).
- 2. Contractor rates are established.
- 3. Contractor is familiar with WUSM safety standards required to perform the work. (Safety Standards are included in this package)
- 4. Contractor should meet sustainable guidelines by salvaging and/or recycling materials. This includes depositing all paper, plastic, glass and metals in designated dumpsters on campus and recycling acoustical ceiling tiles and carpet as much as possible.
- Contractor is to submit a MSDS (Material Safety Data Sheet) verifying that the VOC is under the acceptable maximum limit prior to the start of work. The VOC content limit for the materials and adhesives are listed as part of this package.



Painting and Coatings

For Interior field-applied applications, use paints and coatings that do not exceed the following VOC (Volatile Organic Compounds) content limits:

- <u>Flat paints and Coatings (Including primers)</u> Not more than 50 grams of VOC per liter of coating less water and exempt compounds, including pigments.
- Non- flat Paints and Coatings except high gloss Not more than 150 grams of VOC per liter of coating less water and exempt compounds, including pigments
- Anti-corrosive and anti-rust paints applied to interior ferrous metal substrates Not more than 250 grams of VOC per liter of coating less water and exempt compounds, including pigments
- <u>Clear wood finishes</u> Varnish: Not more than 350 grams of VOC per liter of coating Lacquer: Not more than 550 grams of VOC per liter of coating
- Floor Coatings Not more than 100 grams of VOC per liter of coating
- Stains Not more than 250 grams of VOC per liter of coating
- All epoxy painting & coatings and sealers need to be reviewed with Design & Construction

Notes:

- 1. If there are special circumstances where there is a need to use paints or coatings that exceed the VOC content limits, contact Environmental Health and Safety to have the product reviewed. The contact person for EH & S is Brad King (935-9262).
- 2. Do not paint any Lab counters.

	Painting Contractors
Joseph Ward Painting Co	
8040 Litzsinger	
St. Louis, MO 63144	
314-644-0500	
Contact: Phil Johler	
Slattery Painting	
8461 Delport Drive	
St. Louis, MO 63114	
314-417-7703	
Fax: 314-427-2583	
Contract: Mike Slattery	

Adhesives, Glues and Mastics

The Contractor is to provide a MSDS (Material Safety Data Sheet), prior to the start of work, verifying that the adhesives, glues and mastic VOC's are not more than 50 grams of VOC per liter less water. If there are special circumstances where there is a need to use adhesives, glues or mastics that exceed the VOC content limits, contact Environmental Health and Safety to have the product reviewed. The contact person for EH & S is Brad King (935-9262).

Flooring

Carpeting – General Notes

- 1. Carpet Contractors are to be approved by WUSM Capital Projects. (See Flooring Listing below)
- 2. If your project involves replacing existing carpet or installing carpet over existing VCT flooring, contact WUSM Capital Projects for testing the VCT flooring material and the adhesives underneath for asbestos. It is Federal Law that these tests are completed prior to the start of any work in case the VCT is disturbed when the carpet is removed. Based on the results of the test, WUSM D & C will determine the need for their continued involvement.
- 3. Verify that the Flooring Contractor includes in their estimate for floor preparation. Floor preparation should include:
 - Removal of existing mastic
 - One (1) skim coat to bridge gaps and provide smooth transitions
 - Additional floor prep may be required so that it is acceptable to receive the new flooring material. This will be determined by the carpet installer.
- 4. The Flooring Contractor is to submit a MSDS (Material Safety Data Sheet), prior to the start of work, verifying that the adhesive VOC is not more than 50 grams of VOC per liter less water.
- 5. All carpet and cushion (if used) shall meet the sustainable guidelines. These guidelines require that the carpet be certified and meet the testing and product requirements of the Carpet and Rug Institute's Green Label Plus program.
- 6. All carpet and cushions (if used) shall meet the following Flame Resistant and Smoke Density standards:
 - Flammability: ASTM 648 0.22 watts/cm2 critical radiant flux.
 - Smoke Density: ASTM E662 Rating to be less than 450 in flaming mode and must meet Federal Flammability standard DOC FF 1-70.

VCT & Sheet Vinyl Flooring – General notes

- 1. Review with WUSM Project Manager where sheet vinyl flooring will be used. (See Flooring Listing below)
- 2. Flooring Contractor is to be approved by WUSM Capital Projects Department.
- 3. Verify if new VCT will be installed over existing VCT. This condition should be verified and approved by the flooring Contractor before they submit their estimate.
- 4. Existing VCT or Sheet vinyl should not be removed without notifying a WUSM Project Manager in advance to conduct asbestos testing.
- 5. Verify that the Flooring Contractor includes an estimate for floor preparation. Floor preparation should include:
 - Removal of existing mastic
 - One (1) skim coat for VCT to bridge gaps and provide smooth transitions
 - Two (2) skim coats for sheet vinyl areas to bridge gaps and provide smooth transitions
- 6. The Flooring Contractor is to provide a MSDS (Material Safety Data Sheet), prior to the start of work, verifying that the adhesive VOC is not more than 50 grams of VOC per liter less water.

FLOORING

Flooring Systems, Inc. 4130 Meramec Bottom Rd St. Louis, MO 63129 314-329-9300

Contact: Sherry Bourque

e-mail: sbourque@flooringsystemsinc.net

CI Select Flooring Solutions 1716 Hidden Creek Court St. Louis, MO 63131 314-909-1701

Contact: Ellen Zucker

e-mail: ezucker@ciselect.com

Stephens Flooring 2606 Rock Hill Ind Ct. St. Louis, MO 63144 314-918-9696

Contact: Mike Wood

Zickel Flooring 1555 Fenpark Dr. Fenton, MO 63026 636-343-8663

Contact: Mark Huesgen

e-mail: mark.huesgen@zickel.com

Casework - General Notes

- 1. The particleboard, medium density fiberboard (MDF), plywood and laminating adhesives for the new plastic laminate casework shall contain no urea-formaldehyde resin.
- 2. Verify that the counter is supported by a brace or panel at 3' on center.
- 3. Verify that adjustable shelves be supported by heavy duty standards and secured to backing in the wall.
- 4. Verify if glass containers or chemicals will be installed on the shelves. The material of the shelves should be 3/4" trespa with seismic bars or aluminum edges installed to prevent items from falling off in the event of an earthquake.
- 5. Contact EH&S if existing laboratory countertops are being removed or modified. The solid surface counter and backsplash could contain asbestos.
- 6. Drawer slides. Verify that the contractor provides ball bearing type drawer slides with full extension and has a load capacity of 75 lbs.

00 1	utter Insurance Associ Thomas Company, Inc. Market Street, 18th F Louis MO 63101		ONLY AND HOLDER. T	CONFERS NO R	INTER-5 ED AS A MATTER OF IN IGHTS UPON THE CERT E DOES NOT AMEND, E FORDED BY THE POLICE	TIFICATE EXTEND OR
		14-657-2970	INSURERS AFFORDING COVERAGE			NAIC #
SUREC			INSURER A: Amerisure Insurance Co			19488
			INSURER 8.		induzunos do	13400
	Interface Construc	tion Corn	INSURER C			
	8401 Wabash Berkeley NO 63134		INSURER D:		350	
3231ET 8	TO AND THE PROPERTY OF THE PRO		INSURER E:		3	
	RAGES					
MAY P POLIC	OLICIES OF INSURANCE LISTED BELOW HAV EQUIREMENT, TERM OR CONDITION OF ANY PERTAIN, THE INSURANCE AFFORDED BY TH IES, AGGREGATE LIMITS SHOWN MAY HAVE	CONTRACT OR OTHER DOCUMENT WI E POLICIES DESCRIBED HEREIN IS SUB	ITH RESPECT TO WHICH MECT TO ALL THE TERM	HITHIS CERTIFICATE M VS. EXCLUSIONS AND (IAY BE ISSUED OR	
R ADD	RD TYPE OF INSURANCE	POLICY NUMBER	POLICY EFFECTIVE DATE (MWDDYYYY)	POLICY EXPIRATION DATE (MM/DD/YYYY)	LIMIT	rs
	GENERAL LIABILITY				EACH OCCURRENCE	\$1,000,000
	X COMMERCIAL GENERAL LIABILITY	CPP132588702	06/30/09	06/30/10	DAMAGE (O RENTED PREMISES (Eu groungroe)	s300,000
	CLAIMS MADE X OCCUR				MED EXP (Any 6 ie person)	\$5,000
					PERSONAL & ADV INJURY	\$1,000,000
					GENERAL AGGREGATE	\$2,000,00
	GEN'L AGGREGATE LIMIT APPLIES PER: POLICY X PRO LOC			2 7 7	PRODUCTS - COMP/OP AGG	\$2,000,00
	AUTOMOBILE LIABILITY				Proposition of the proposition of the state	
1	X ANY AUTO	CA132588602	06/30/09	06/30/10	COMBINED SINGLE LIMIT (Falacaident)	\$1,000,000
	GARAGE ANY				H.	
	- mandagaga	CU1325888	06/30/09	06/30/10	EACH OCCURRENCE AGGREGATE	
	EXCESS / UMDRELLA LIABILITY X UCCUR CLAIMS MADE DEDUCTIBLE	CU1325888	06/30/09	06/30/10	1	
w	EXCESS / UMBRELLA LIABILITY X UCCUR CLAIMS MADE DEDUCTIBLE X RETENTION S O ORKERS COMPENSATION	CU1325888	06/30/09	06/30/10	AGGREGATE	\$ 1,000,000 \$ \$
WO	EXCESS / UMBRELLA LIABILITY X UCCUR CLAIMS MADE DEDUCTIBLE X RETENTION S 0 ORKERS COMPENSATION OR DEMPLOYERS 'LIABILITY X NAME OF THE ORIGINAL OR THE ORI			19 20	AGGREGATE X WC STATU OTH- X TORY LIMITS ER	\$ 1,000,000 \$ \$ \$
WC AN AN	EXCESS / UMBRELLA LIABILITY X QCCUR CLAIMS MADE DEDUCTIBLE X RETENTION S 0 DOKKERS COMPENSATION RD EMPLOYERS LIABILITY IV PROPRIETCH/PARTINIC/RCCUTTY TECRY/MEMBERS RECULORED TO COMPENSATION TECRY/MEMBERS RECULORED	CU1325888 WC1325889	06/30/09	06/30/10	AGGREGATE X WC STATU. OTH- X TORY IMITS ER	\$ 1,000,000 \$ \$ \$ \$ \$ \$ \$
AA OF (M)	EXCESS / UMBRELLA LIABILITY X UCCUR CLAIMS MARE DEDUCTIBLE X RETENTION S O ORKERS COMPENSATION OF MARCONERS LIABILITY YYN VEROPRIETORYSEATORS COLUMNS			19 20	AGGREGATE X WC STATU OTH- X TORY LIMITS ER	\$ 1,000,000 \$ 5 \$ 5 \$ 5 \$ 500,000
AN OF (M II) SF	EXCESS / UMBRELLA LIABILITY X UCCUR CLAIMS MADE DEDUCTIBLE X RETENTION S 0 ORKERS COMPENSATION OF EMPLOYERS LIABILITY Y (N TECEPHICHMER COCCUPIES AND	WC1325889	06/30/09	06/30/10	AGGREGATE X WC STATUL OTH- X TORY IMITS ER E.: EAGH ACCIDENT E.U DISEASE - EA EMPLOYEE	\$ 1,000,000 \$ 5 \$ 5 \$ 5 \$ 500,000
WMAN AN OIT OIT SCRIF ROJ ASH NSU	EXCESS / UMBRELLA LIABILITY X UCCUR CLAIMS MARE DEDUCTIBLE X RETENTION S O DIRECTOR SOME STATEMENT OF THE CONTROL OF THE C	WC1325889 ELES/EXCLUSIONS ADDED BY ENDOR: 6 4565 MCKINLEY - DE OOL OF MEDICINE IS I	06/30/09 SEMENT/SPECIAL PRO SMO BASEMENTA INCLUDED AS R THE GENERA	06/30/10 OVISIONS AREA AN ADDITION L LIABILITY	AGGREGATE X TORYLINITS ER E. EACH ACCIDENT EL DISEASE - EA EMPLOYEE EL DISEASE POLICYLINIT AL POLICY	\$ 500,000 \$ 500,000 \$ 500,000
WO AN	EXCESS / UMDRELLA LIABILITY X UCCUR CLAIMS MADE DEDUCTIBLE X RETENTION S 0 DORKERS COMPENSATION RD EMPLOYERS LIABILITY Y/N VENOPHET CORPORTER CACCUTTES TECLEMENTED REVENUE COLUMN TECLEMENT OF OPERATIONS / LOCATIONS / VEHICLE PTION OPERATIONS / LOCATIONS / VEHICLE PTION OPERATIONS / LOCATIONS / VEHICLE PTION OPERA	WC1325889 ELES/EXCLUSIONS ADDED BY ENDOR: 6 4565 MCKINLEY - DE OOL OF MEDICINE IS I	06/30/09 SEMENT/SPECIAL PRO SMO BASEMENT INCLUDED AS R THE GENERA INSURED FOR CANCELLAT	06/30/10 OVISIONS AREA. AN ADDITION L LIABILITY THE CERTIFI	AGGREGATE X TORYLINITS ER E. EACH ACCIDENT EL DISEASE - EA EMPLOYEE EL DISEASE POLICYLINIT AL POLICY	\$ 1,000,000 \$ \$ \$ \$ \$ 500,000 \$ 500,000