SECTION 10 28 00 – TOILET ROOM ACCESSORIES

PART 1 – GENERAL

During the construction document process, the architect shall coordinate with the WUSM project manager, all toilet room accessories, accessory locations and quantities. All toilet room accessories shall be graphically indicated on the plans (floor plans and elevations).

PART 2 – PRODUCTS

Accessories shall be furnished and installed as follows:

Accessory	Furnish by	Install by
Paper towel dispensers	owner	contractor
Soap dispensers	owner	contractor
Trash and waste receptacles	owner	owner
Roll paper holders	owner	contractor
Grab bars	contractor	contractor
Coat hooks	contractor	contractor
Baby changing stations	contractor	contractor
Framed mirrors	contractor	contractor
Unframed mirrors	contractor	contractor
Accessible shower seat	contractor	contractor

Baby changing stations shall be provided in both men's and women's multi stall and single accommodation toilet rooms in public areas. Built in baby changing stations shall be by exception only. Where built in they shall be of the same material as the lavatory counters.

, sanitary napkin disposals and recessed paper towel dispenser & disposal units are by exception only and must be approved by the WUSM project manager. Toilet seat cover dispensers and sanitary napkin dispensers shall not be provided.

PART 3 – EXECUTION

Install accessories in accordance with manufacturers written instructions. All devices shall be installed in compliance with the latest edition of the American with Disabilities Act (ADA) and all governing accessibility codes and written directives from the City of St. Louis.

END OF SECTION